DOOR SCHEDULE

OPENING				OPENING SIZE		DOOR			FRAME				
ROOM NUMBER	TAG	RM NAME	RATING	WIDTH	HEIGHT	MATERIAL	FINISH	GLASS TYPE	TYPE	MATERIAL	FINISH	HARDWARE	REMARKS
201	201	MEETING	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
202	202	MEETING	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	203		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	204		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	205		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	206		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
207	207A	CONFERENCE	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
207	207B	CONFERENCE	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
208	208	MEETING	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
255	209	RECEPTION	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
210	210	MEETING	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
211	211A	CONFERENCE	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
211	211B	CONFERENCE	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
212	212	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
213	213	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
214	214	MEETING	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
215	215	MEETING	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
218	216	OPEN OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
218	217	OPEN OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	223		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	224		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	225		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	226		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
227	227	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	228		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	229		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	230		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
233	231	BREAK	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
233	232	BREAK	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
234	234	MEETING	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
235	235	MEETING	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
236	236	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
237	237	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	238		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
239	239	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
240	240	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
241	241	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
242	242	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
243	243	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
245	245	MEETING	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
246	246A	CONFERENCE	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
246	246B	CONFERENCE	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
247	247	MEETING	NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
249	249	OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
250	250	COPY	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
251	251	STAIR	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	252		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
255	253	RECEPTION	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
253A	253A	STORAGE	NR	2' - 10"	6' - 8"								
254	254	WOMEN'S RR	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
254	254A	WOMEN'S RR	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	254B		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
257	257	SERVER	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	258		NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
258A	258A	STORAGE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
258	258B	MEN'S RR	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
259	259	STAIR	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
255	260	RECEPTION	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
263	261	OPEN OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
263	262	OPEN OFFICE	NR	3' - 0"	7' - 0"	HM	P1A	NA	HM	HM	PAINT P3	5A	
	264		NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
	265A		NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
	265B		NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	
	266		NR	2' - 10"	6' - 8"	WD	P3	GL2	WD	WD	PAINT P2	2B	

Level 02: 64
Grand total: 64

DOOR / WINDOW ABREVIATIONS

ALUM =	ALUMINUM	P =	PAINT
BF =	BI-FOLD	PH =	PANIC HARDWARE
CL =	CLOSET	PR =	PAIR
GL =	GLASS	PF =	PRE-FINISHED
HCW =	HOLLOW CORE WOOD	RM =	REMOVABLE MULLION
HM =	HOLLOW METAL	RO =	ROUGH OPENING
CF =	CLEAR FINISH	SCW =	SOLID CORE WOOD
CP =	COPPER	STL =	STEEL
CSMT =	CASEMENT	T -	TEMPERED
FA =	FACTORY	TR =	TERRACE
FX =	FIXED	VGDF =	VERTICAL GRAIN DOUGLAS
HDG =	HDG	WD =	FIR
LG =	LAMINATED GLASS	SS =	WOOD
MANUF. =	MANUFACTURED	ST=	SMOKE SEAL
CLR ANNOD. =	CLEAR ANNODIZED	§ =	STAIN
			SECURITY PROVISIONS APPLY

GENERAL DOOR NOTES

1. REFER TO PLAN DRAWINGS FOR SWINGS OF DOORS.

2. ALL GLAZING IN DOORS TO BE TEMPERED.

3. FIELD VERIFY ALL CONDITIONS FOR PLACEMENT, SIZE, DETAILS.

4. UNDERCUT DOOR FOR MINIMUM CLEARANCE ABOVE FLOOR FINISH.

5. PROVIDE DOOR SCHEDULE SHOP DRAWINGS AND HARDWARE SPECIFICATIONS FOR
ARCHITECT'S APPROVAL.

6. WHIERE A PAIR OF DOORS IS UTILIZED, AT LEAST ONE OF THE DOORS SHALL PROVIDE
A CLEAR, UNOBSTRUCTED OPENING OF 32 INCHES WITH THE LEAF POSITIONED AT AN
ANGLE OF 90 DEGREES FROM ITS CLOSED POSITION. (1133B.2.3.1)

7. THE BOTTOM 10 INCHES OF ALL DOORS EXCEPT AUTOMATIC AND SLIDING SHALL HAVE A SMOOTH, UNINTERRUPTED SURFACE TO ALLOW THE DOOR TO BE OPENED
BY A WHEELCHAIR FOOTREST WITHOUT CREATING A TRAP OR HAZARDOUS CONDITION. WHERE NARROW FRAME DOORS ARE USED, A 10 INCH HIGH SMOOTH
PANEL SHALL BE INSTALLED ON THE PUSH SIDE OF THE DOOR, WHICH WILL ALLOW
THE DOOR TO BE OPENED BY A WHEELCHAIR FOOTREST WITHOUT CREATING A TRAP OR HAZARDOUS CONDITION.

DOOR HARDWARE NOTES

1. THE GENERAL CONTRACTOR SHALL PROVIDE AND INSTALL REQUIRED BUCK ASSEMBLIES AS SHOWN ON ARCHITECTS DRAWINGS, U.N.O.

2. THE GENERAL CONTRACTOR SHALL PROVIDE AND INSTALL DOORS AS SPECIFIED ON
ARCHITECTURAL DRAWINGS, U.N.O.

3. COORDINATE KEYING OF EXISTING DOORS WITH NEW DOORS ALIKE. ALL ENTRANCE/EXITS TO BE KEYED ALIKE U.N.O. ALL PRIVATE OFFICES TO BE KEYED SEPARATELY UN.O. ALL SUPPORT ROOMS TO BE KEYED ALIKE U.N.O. COORDINATE MASTER KEYING WITH TENANT, LANDLORD, AND ARCHITECT. KEYING TO BE REFLECTED ON DOOR AND HARDWARE SUBMITTAL.

4. ALL LOCKSETS SHALL BE CODED AND/OR KEYED IN ACCORDANCE WITH THE BUILDING REQUIREMENTS. CODES AND/OR KEYS ARE TO BE DELIVERED TO TENANT
PROPERLY TESTED AND/OR TAGGED. THE NUMBER OF MASTER AND PASS KEYS SHALL BE COORDINATED WITH BUILDING MANAGEMENT.

5. CONTRACTOR SHALL SUBMIT A DETAILED HARDWARE LIST WHICH INDICATES THE QUANTITIES, TYPES, MANUFACTURERS, CATALOG NUMBERS AND LOCATIONS OF THE
VARIOUS ARTICLES OF HARDWARE REQUIRED. HARDWARE LIST SHALL BE SUBMITTED NO LATER THAN (30) DAYS BEFORE THE DATE THE SUPPLIER MUST PLACE THE ORDER WITH THE MANUFACTURERS IN ORDER TO MEET THE PROJECT SCHEDULE. REVIEW OF THE HARDWARE LIST BY ARCHITECT SHALL NOT BE CONSTRUED AS CERTIFYING THAT THE LIST IS COMPLETE AND DOES NOT RELIEVE THE CONTRACTOR FROM PROVIDING A COMPLETE PROJECT.

6. EACH ARTICLE OF HARDWARE SHALL BE INDIVIDUALLY PACKAGED IN ITS MANUFACTURERS CONTAINER; PROPERLY MARKED OR LABELED IN CONFORMITY WITH THE APPROVED HARDWARE LIST.

7. ALL HARDWARE APPLIED TO METAL DOORS OR JAMBS SHALL BE MADE TO TEMPLATE
AND SHALL BE SECURED BY MACHINE SCREWS.

8. FURNISH TWO BUTT HINGES FOR DOORS UP TO 5 FT. HIGH AND ONE ADDITIONAL BUTT FOR EACH 2 1/2 FT.

9. CONTRACTOR SHALL FURNISH STANDARD STRIKE PLATES WITH EXTENDED LIPS WHERE REQUIRED TO PROTECT TRIM FROM BEING MARRED OR DAMAGED BY THE \
LATCH BOLT.

10. CONTRACTOR SHALL PROVIDE DUST COVERS AT ALL STRIKE PLATES.

11. HARDWARE SUPPLIER SHALL PROVIDE GRANDMASTER KEY MASTER KEY, KEY-ALIKE
AND/OR KEY-DIFFERENT ALL LOCKS IN ACCORDANCE WITH KEYING SCHEDULE PROVIDED BY THE TENANT.

12. ALL FASTENERS SHALL MATCH THE HARDWARE MATERIAL AND FINISH.

13. REUSE EXISTING DOOR HARDWARE, IF POSSIBLE, TO ACCOMMODATE SPECIFIED HARDWARE SET. G.C. TO FIELD VERIFY EXISTING HARDWARE AND DETERMINE IF ANY
NEW/REPLACEMENT COMPONENTS ARE REQ'D. CLEAN & REPAIR EXISTING HARDWARE (THAT IS TO REMAIN) TO APPEAR AS NEW.

14. THE ATTACHED HARDWARE SCHEDULE IS INTENDED TO COVER ALL DOORS IN THE
PROJECT AND ESTABLISH A TYPE AND STANDARD OF QUALITY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FURNISH A COMPLETE AND OPERATIONAL SYSTEM OF DOOR FINISH HARDWARE ITEMS, ENCOMPASSING ALL OPENINGS WITHIN THE PROJECT AREA.

15. IT IS THE RESPONSIBILITY OF CONTRACTOR TO REPLACE ANY AND ALL DOOR HARDWARE ITEMS THAT DO NOT COMPLY WITH CURRENT DISABLED ACCESSIBILITY
PROVISIONS, WITH CONFORMING ITEMS, TO THE SATISFACTION OF THE BUILDING AUTHORITY.

16. HAND ACTIVATED DOOR OPENING HARDWARE SHALL BE CENTERED NOT LESS THAN
30" NOR MORE THAN 44" HIGH AND SHALL BE OPERABLE WITH A SINGLE EFFORT NOT
REQUIRING GRASPING OF THE OPENING HARDWARE PER CBC 1132A.8.

17. CLOSERS, WHERE REQUIRED, SHALL HAVE AN OPENING FORCE NOT EXCEEDING 8.5
LBS FOR EXTERIOR DOORS AND 5 LBS FOR INTERIOR DOORS WITH THE EXCEPTION
OF FIRE-RATED DOORS WHICH MAY NOT EXCEED 15 LBS.

18. THRESHOLDS SHALL NOT BE GREATER THAN 1/2" IN TOTAL HEIGHT WITH THE LEADING EDGES REVEALED OR SLOPED AT AN ANGLE NOT EXCEEDING 45 DEGREES
SO THAT NO SINGLE VERTICAL CHANGE OF ELEVATION EXCEEDS 1/4".

19. THE BOTTOM 10" OF ALL DOORS (EXCEPT AUTOMATIC AND SLIDING) SHALL HAVE A
SMOOTH UNINTERRUPTED SURFACE. NARROW FRAME DOORS SHALL BE EQUIPPED
WITH A 10" HIGH SMOOTH PANEL ON THE PUSH SIDE OF THE DOOR.

20. DOOR STOPS OF IN-SWINGING DOORS SHALL BE OF ONE PIECE CONSTRUCTION WITH THE JAMB OR JOINED BY RABBET TO THE JAMB, U.N.O.

21. ALL PIN TYPE HINGES WHICH ARE ACCESSIBLE FROM OUTSIDE THE SECURED AREA
WHEN THE DOOR IS CLOSED SHALL HAVE NON-REMOVABLE HINGE PINS. IN ADDITION, THEY SHALL HAVE MINIMUM 1/4" DIAMETER STEEL JAMB STUD WITH 1/4" MINIMUM PROJECTION UNLESS THE HINGES ARE SHAPED TO PREVENT REMOVAL OF THE DOOR IF THE HINGE PINS ARE REMOVED.

22. THE STRIKE PLATE FOR LATCHES AND THE HOLDING DEVICE FOR PROJECTING DEAD
BOLTS IN WOOD CONSTRUCTION SHALL BE SECURED TO THE JAMB AND THE WALL
FRAMING WITH SCREWS NOT LESS THAN 2 1/4" IN LENGTH.

23. REFER TO GENERAL NOTES AND RESPECTIVE DOOR SCHEDULE SHEETS FOR ADDITIONAL NOTES ON DOORS, FRAMES AND HARDWARE.

24. ALL ALUMINUM DOOR FRAMES NOT IN STORE FRONT SYSTEM SHALL BE MANUFACTURED BY **WESTERN INTEGRATED** COLOR- CLEAR ANODIZED ALUMINUM.
PROFILE TO MATCH DRAWING. FRAMES TO BE FURNISHED WITH MITERED CORNERS. PAINTED FRAMES ARE TO BE FACTORY FINISHED, COLOR AS NOTED ABOVE. SUBMIT SAMPLE TO ARCHITECT FOR APPROVAL PRIOR TO FABRICATION.

25. CONTRACTOR SHALL FURNISH ALL HARDWARE AS REQUIRED TO MEET CODE AND FUNCTIONAL INTENTIONS AND REQUIREMENTS. THE FOLLOWING OUTLINE HARDWARE SPECIFICATION IS PROVIDED AS A BASIS FOR A COMPLETE SUBCONTRACTOR SUBMITTAL. HARDWARE SUBMITTAL SHALL BE SUBJECT TO ARCHITECTS APPROVAL.

26. COORDINATE ELECTRIC LOCK WITHIN SPECIFICATIONS AND REQUIREMENTS WITH
OWNERS SECURITY CONSULTANT.

27. LATCHING AND LOCKING DOORS THAT ARE HAND ACTIVATED AND WHICH ARE IN A PATH OF TRAVEL SHALL BE OPRRABLE BY LEVER TYPR HARDWARE, PANIC BARS, PUSH-PULL ACTIVATED BARS, U-SHAPED HANDLES, OR OTHER HARDWARE DESIGNED TO PROVIDE PASSAGE WITHOUT REQUIRING THE ABILITY TO GRASP

BLUEBEAM®
A NEMETSCHEK COMPANY

CAPTURE ENGINEERS
Mechanical
Electrical
Plumbing

1234 Miller St.
Manchester, NH 06930

REVU ARCHITECTS

5555 N. Broad St
Pasadena CA 91101

OFFICE BUILDING

Project No: 323232

Project Address:
123 Schonsett St
Chicago, IL 60601

THIS DRAWING IS INTENDED FOR DEMONSTRATION PURPOSES ONLY. DO NOT USE THIS DRAWING FOR ANY OTHER PURPOSE WITHOUT THE EXPRESS WRITTEN PERMISSION OF BLUEBEAM, INC.

DATE	03/04/2018
ISSUED FOR:	INTERNAL REVIEW
PROJECT	3232
DRAWN BY:	Author
CHECKED BY:	Checker
APPROVED BY:	Approver

#	DATE	DESCRIPTION

NOT FOR CONSTRUCTION

STAMP:

STAMP:

SHEET TITLE & NUMBER
DOOR SCHEDULE

A8.01

© 2018 Bluebeam, Inc.